

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
POWAI, MUMBAI – 400 076.


Date :03rd , April,2025

Ref: EO/A/ACAD/WKS-178/24-25


Name of Work : Renovation, Refurbishment, Additions & Alterations to Victor Menezes Convention Centre for Civil, Structural, Repairs & Façade works at IIT Bombay, Powai, Mumbai – 400076.

Minutes of pre-bid meeting held on 03.04.2025 at 15:00 hrs in the Conference room of the Estate Office. The following queries were raised by the vendors which are as follows:

Sr. No.	Queries/Doubts by the agencies	Clarifications
1.	In many items, the structural steel YST255 grade is considered; is it for hollow sections or rolled?	It is mainly for hollow sections, and the material will be used according to the drawings provided.
2.	Drawings for reference were not available on the portal.	It will be uploaded as soon as it is obtained from the Architect. (Tentatively on 08.04.2025)
3.	Detail drawings for item no. 7.17, 7.18 are not available for reference.	It will be uploaded as soon as it is obtained from the Architect. (Tentatively on 08.04.2025)
4.	Dynamic load test, mentioned in item no. 1.3- Is it within the contractor's scope?	Yes, it is in the contractor's scope.
5.	M30 grade concrete is considered for constructing the RCC bored pile. Will the reinforcement measurements be considered separately?	Yes, the measurements of concrete and reinforcement for the RCC bored pile will be paid for separately.
6.	Detail drawings for item no. 7.5 is not available for reference.	It will be uploaded as soon as it is obtained from the Architect. (Tentatively on 08.04.2025)
7.	Detail drawings for item no. 7.10 is not available for reference.	It will be uploaded as soon as it is obtained from the Architect. (Tentatively on 08.04.2025)


8/4/25
Executive Engineer (ACLWP)

PSS
P. S. Sawant
for RELEASE
08/04/25.


819